



MAINTENANCE SERVICES CONTRACT

EXHIBIT C

Other Requirements

As used in this Exhibit C, Contractor refers to **MATRIX HG INC.** The Contractor shall comply with the following requirements as checked below:

AA **DIFFERING SITE CONDITIONS**

Contractor shall promptly, and before such conditions are disturbed, notify the Director of Public Works in writing of:

- A. Material that Contractor believes may be material that is hazardous waste, as defined in California Health and Safety Code Section 25117, that is required to be removed to a Class I, Class II or class III disposal site in accordance with provisions of existing law;
- B. Subsurface or latent physical conditions differing materially from those indicated in this Contract; or
- C. Unknown physical conditions, of an unusual nature, differing materially from those ordinarily encountered and generally recognized as inherent in work of the character provided for in this Contract.

The Director of Public Works shall promptly investigate the conditions. If the Director of Public Works finds that such conditions do materially differ and cause an increase or decrease in Contractor's cost of, or the time required for, performance of any part of the work under this Contract, whether or not changed as a result of such conditions, an equitable adjustment shall be made and the Contract modified in accordance with the change order procedures set forth herein.

In the event of any dispute between City and Contractor over the significance or existence of the changed conditions, Contractor shall not be excused from the scheduled completion date set forth herein, but shall retain such rights it may have as provided in these Contract Documents.

No claim of Contractor under this clause shall be allowed unless Contractor has given the notice required by this section, except that City may extend the prescribed time. No claim by Contractor for an equitable adjustment under this provision shall be allowed if asserted after final payment under this Contract.

 **TRAFFIC CONTROL MEASURES**

Contractor shall provide appropriate vehicular, pedestrian and bicycle traffic control measures.

- A. Where facilities exist, a minimum sidewalk and bike path width of four (4) feet shall be maintained at all times for safe passage through the work area. At no time shall pedestrians be diverted onto a portion of the street used for vehicular traffic. At locations where adjacent alternate walkways cannot be provided, appropriate signs and barricades shall be installed at the limits of the construction site and in advance of the closure of the nearest crosswalk or intersection to divert pedestrians across the street. Access shall be maintained for persons with disabilities.

- B. All Work shall be planned and carried out so that there is the least possible inconvenience to vehicular traffic, including deliveries to adjacent properties. Warning signs, lights and safety devices and other measures shall conform to the requirements of the Manual of Traffic Controls issued by Caltrans. Traffic control for day or nighttime lane closures (if nighttime work is permitted) shall be in conformance with the Caltrans Standard Plans for Traffic Control Systems. Contractor is authorized to place properly attired flagger(s) to stop and warn traffic. Traffic shall not be unreasonably delayed. Flagging procedures shall be in conformance with the Instructions to Flaggers pamphlet and/or Manual of Traffic Controls for Construction and Maintenance Work Zones issues by Caltrans.

 **AIR POLLUTION CONTROL**

Contractor shall comply with all air pollution control rules, regulations, ordinances and statutes which apply to any Work performed pursuant to the Contract. Material to be disposed of shall not be burned, either inside or outside the Work site.

 **WATER POLLUTION CONTROL**

Contractor shall exercise every reasonable precaution to protect streams, lakes, reservoirs, bays and coastal waters from pollution with fuels, oils, bitumens, calcium chloride and other harmful materials and shall conduct and schedule its operations so as to avoid or minimize muddying and silting of said streams, lakes, reservoirs, bays and coastal waters. Care shall be exercised to preserve roadside vegetation beyond the limits of construction.


 **STORM WATER POLLUTION PREVENTION STANDARDS**

Contractor shall comply with City's Storm Water Pollution Prevention standards at all times during operation of this contract by incorporating current Best Management Practices (BMP) for use during the work.




SOUND CONTROL REQUIREMENTS

Contractor shall comply with all local sound control and noise level rules, regulations and ordinances which apply to any work performed pursuant to the Contract. Each internal combustion engine, used for any purpose on the job or related to the job, shall be equipped with a muffler of a type recommended by the manufacturer.



WEIGHT LIMITATIONS

Unless expressly permitted by the Director of Public Works, Contractor shall not operate construction equipment or vehicles of any kind which, laden or unladen, exceed the maximum weight limits set forth in Division 15 of the California Vehicle Code over completed or existing base, surfacing, pavement or structures.




SUBSURFACE EXCAVATIONS; NOTIFICATION

Attention is directed to Government Code Sections 4216 to 4216.9, and in particular Section 4216.2 which provides, in part:


"Except in an emergency, every person planning to conduct any excavation shall contact the appropriate regional notification center at least two working days, but no more than 14 calendar days, prior to commencing that excavation, if the excavation will be conducted in an area which is known, or reasonably should be known, to contain subsurface installations other than the underground facilities owned or operated by the excavator, and, if practical, the excavator shall delineate with white paint or other suitable markings the area to be excavated. The regional notification center shall provide an inquiry identification number to the person who contacts the center and shall notify any member, if known, who has a subsurface installation in the area of the proposed excavation."

Contractor shall contact the regional notification center, "Underground Service Alert," and schedule the Work to allow ample time for the center to notify its members and, if necessary, for any member to field locate and mark its facilities.



TRENCH EXCAVATION SAFETY PLAN

Attention is directed to California Labor Code, Section 6705. At least five (5) days in advance of excavation of any trench five feet or more in depth, Contractor shall submit to the Director of Public Works a detailed plan showing the design of shoring, bracing, sloping and other provisions to be made for worker protection from the hazard of caving ground during the excavation of such trench or trenches. If such plan varies from the shoring system standards established by the State Construction Safety Orders, the plan shall be prepared and signed by a registered civil or structural engineer. Nothing in this section shall be deemed to allow the use of a shoring, sloping or protective system less effective than that required by the Construction Safety Orders of the Division of Industrial Safety. Nothing in this section shall be construed to impose liability on City or its employees or agents.



HAZARDOUS CHEMICALS AND WASTES

Should any release, discharge, leakage, spillage, emission or pollution of any hazardous chemicals or wastes occur due to Contractor's acts or omissions, then Contractor at its sole cost, shall clean all affected property to the satisfaction of City and any governmental body with jurisdiction. Contractor shall immediately report any such release to the Director of Public Works.

If the performance of the Work outlined by these Contract Documents creates any hazardous wastes, Contractor shall properly dispose of such wastes in full accordance with federal, state and local laws, at its expense. Contractor shall provide City with written proof of its or its subcontractor's registration as a hazardous waste transporter.

OTHER REQUIREMENTS

Use this space to list any other requirements not stated above.

Click to start typing...